

a division of Englobe

Proud of Our Past... Building the Future

#### INFRASTRUCTURE AUDIT

Village of Bittern Lake

# **Project Objective**

- Assess the current condition of key infrastructure
- Recommend infrastructure upgrades considering:
  - Existing condition
  - Current standards and guidelines
- Develop cost estimates and priority for completion
- Allocation of funds to infrastructure with the most need
- **Grant funding**

## **Study Scope**

- Introductory meeting with Village staff
- Review available information
- Inspect key infrastructure
- Identify required upgrades and maintenance
- Develop a Class D Cost Estimate
- Develop a 20 Year Capital Plan

## **Key Infrastructure**

- Potable Water Supply and Distribution
- Sanitary Collection and Treatment
- Stormwater
- Transportation
- Village owned buildings
- Waste Transfer Site
- Vehicles and Equipment

## **Historical Water Consumption**

- ADD = Average Day Demand
- D MDD = Max Day Demand
- PHD = Peak Hour Demand
- □ Lpcd = Litres per capita per day

	Historical Consumption (Lpcd)	Audit Values (Lpcd)					
ADD	228	250					
MDD	552	500					
PHD	1,104	1,000					

## Water Supply and Storage

- City of Camrose
- Reservoir and Pump Station
- Reservoir Capacity =  $550 \text{ m}^3$
- Required Storage for Typical
  Consumption = 163 m<sup>3</sup>
- Storage recommended for
  Fire Demand = 540m<sup>3</sup>



### **Pump Station**

- Adequate ConditionOverall
- Continue Maintenance
- Implement SCADA



## Water Distribution System



- Record Drawings
- □ GPS Survey
  - Valves
  - Hydrants
- Hydrant Flow Testing
- History of breaks or leaks

## Water System Modeling

- System Layout
- Historical Water Demands
- □ Fire Flows
- Hydrant Testing
- Results
  - Adequate Pressure
  - Limited Fire Flow



### Water System Improvements

#### Looping

Increasing Watermain Diameters

- Additional Hydrants
- Fire Demand Review



### **Sanitary Collection**



- □ 2015 Drawings
- □ GPS Survey
  - Manholes
- Manhole inspections
- Sanitary main camera inspection footage

### **Manhole Inspections**

#### Material

- Concrete
- Brick

#### Surface

- Inflow
- Top Slab and Collars
- □ Ladder rungs
- Barrels
- Base and pipe leads
- Measure pipe inverts



Engineering Lt.

Manhole Inspection Checklist

Town or Village:															
MH Location or Number:	A Location or Number:														
Barrel Diameter:		Notes:													
Manhole Type:	5A.	5A 1-5 Depp													
Collar Material:	Camcrete		firick.			Other									
Berrel Material:	Concrete		Block			Other	T								
Bench Material:	Presaut		Field.			Other	IC		1						
Parson Insert Installed: 110/144															
Item Rate: Notes															
Surface (Rati	e 1-5 with	1 bein	g low and 5	bei	ing I	Ngh]									
Opes surface water drain a	way from	the l	NH	_			•			No / Te	8	1.5	9		
Is the lid matched to MH t	ype (San,	Storm	, Town Log	;o)						No / Ye	1	1			
is the frame flush to match	the road	grade	e (15 mm t	ole	rana	ce)				No./Ye		6			
Comments and Photo Nur	nbers						_	_							
Top Slab & Collars (Rot	e 1-5 with	1 bein	g low and 5	be	ing i	high)				January .					
Are there between 1 and 3	collars in	use.								No / Ye	5				
is the total height of collar	sbetwee	n 50 m	nm - 305 m	1171						No/Ye	5				
is the grouting complete a	nd without	it gap	2							No/7e	5	1. J			
Free from evidence of leak	ing or wa	ter sta	sins							No / Ye	8	2			
Comments and Photo Numbers															
Steps of Ladder (Rate 1-5 with 1 being low and 5 being high)															
Is the top step within 400 mm from lid No / Yes															
Is the bottom step within 400 mm of the base No / Yes															
Do the steps line up (within 40 mm tolerance, 20 mm dia min. Std.) No / Yes															
Are the steps twisted No / Tes															
Are the steps corroded or	damaged	naged							No / Ye	1					
Steps are below the MH lie	and not	id not on the opposite wall of MH Nu / Yes													
Comments and Photo Numbers															
MH Barrels (Rate 1-5 with 1 being low and 5 being high)															
Are there cracks or damage to the MH side walls Nor/Yes															
Do the sides of the barrel have evidence of water stains or weeping No / Yes															
to the joints between barrels have evidence of leakage through joints								No/Ye	8	8					
Are there unfilled open weeping holes in the sides of the storm MHs No / Yes															
Comments and Photo Numbers															
MH Base and Leads (Rat	te 1-5 with	1 bein	g low and 3	i be	ing	high)									
Base and Channels are smo	ooth with	out es	idence of	cor	rasi	on or c	oner	ete	wear	r No/Te	a	4			
Leads into the MH stop at the springline, which is flush to inside wall of MH No / Yes															
Sides are benched in MH floor for San, & Storm leads over 600 mm Nu / Yuu 🛛															
Are there service leads directly into the MH - i.e. cul de sacs No / Yes															
Is the distance less than 760 mm from all inlet inverts to springline of outlet No / Yes															
Inverts are properly sealed and grouted No / tes															
Channels are free from rocks and dirt which might indicate break in line No / Yes															
MH base is free of sewage	H base is free of sewage settlement due to slow flow or blockage Nu / Yws														
Comments and Photo Numbers															

	SW	5	SE	E	NE	N	NW	W		
Size of Inserts										
Rim to Invert Elev.						1				

## Manhole Condition Assessment

- □ 21% Good Condition
- □ 45% Fair Condition
- □ 24% Poor Condition
- □ 10% couldn't be inspected
- a 3 manholes for replacement
- □ 13 manholes for repairs

## Sanitary Main Camera Inspection





- Cracks
- Exposed Gaskets
- Breaks
- Joint offsets/ gaps
- □ Sags
- Intrusions
  - Services
  - Roots
  - Mineral deposits

## Sanitary Main Condition Assessment

Rating	Percentage (%)
Good	22
Fair	37
Poor	34
Not Rated	7

- Replacement
- Relining
- Spot Repairs
- In Modeling

## Sanitary Collection System Priority Level



### **Sanitary Treatment**



- Single Cell
- Capacity
- Configuration

## **Lagoon Condition**



- Significant Vegetation Growth
- No Erosion
- Inlet Structure
- **D** Fence Requires Repair



#### **Stormwater Assessment**

#### Contour Data

- System layout
  - Drainage paths
  - Catch basins
  - Culverts
- GPS Survey
- Collect rainfall data
  - Intensity Duration Frequency Curves
  - Various Events



### **Stormwater Model**



Model

- Results
  - Flow rates and volumes
  - Areas and extents of ponding
- Model improvements

## **Transportation Infrastructure**



- □ Field survey
- Record surface deformations
- Summarize pavement condition
- Create maps of Village roads and sidewalks

## **Roadway Condition**

#### Recommend rehabilitation

• Full Mill and Overlay



# **Building Inspections**

- Village owned buildings:
  - Village Office
  - Public Works Shop
  - Community Hall
  - Skate Park/ Skating Rink
  - Cemetery Site
- Assessment:
  - Civil
  - Structural
  - Mechanical
  - Electrical

## Village Office

#### Deficiencies:

- Exterior Siding
- Crack in the Foundation
- Doors and Overhead Doors
- Carpet
- Furnace
- Washroom Exhaust Fan
- Condenser
- Exit Sign Lighting
- Light Fixtures



## **Public Works Shop**



Deficiencies:

- Mezzanine Column
- Exhaust Switch

### **Community Hall**

#### Deficiencies:

- Railing Fasteners
- Exterior Siding
- Painted Surfaces
- Possible Hazardous Materials
- Furnace
- Washroom Exhausts
- Light Fixtures



## **Skate Park and Skating Rink**



- Deficiencies:
  - Exterior Siding

#### Cemetery



- Deficiencies:
  - None

#### **Other Infrastructure**

#### Other Assessments

- Waste Transfer Site
- Inventory of Village
  Owned Equipment



#### **Phase I ESA**

- Completed for Village Owned Sites:
  - Skate Park
  - Village Office
  - Public Works
    Compound
  - Public Works Shop
  - Community Hall
  - Waste Transfer Site
  - Cemetery

- Low Environmental Risk:
  - Skate Park
  - Public Works Shop
  - Waste Transfer Site
  - Cemetery
- Village Office
  - Possible soil contamination
  - Possible hazardous materials
- Public Works Compound
  - Possible soil contamination
- Community Hall
  - Possible soil contamination
  - Possible hazardous materials

### Deliverables

#### Report

- Summary of findings
- Figures for each system
- Cost Estimates for each system
- 20-Year Capital Plan
- Inspection Reports
  - Hydrant flow test reports
  - Manhole inspections
- Models
  - Water System
  - Sanitary System
  - Stormwater